EXTRA ITEM RATE LIST

Name of Work: Improvements to Roads and Drains at Telecom Layout Roads and Surrounding areas in Ward No. 13, (Doddabommasandra).

Name of Agency: M/s. Sri Maruthi Enterprises, Smt. Shashikala, Jinkabachanahalli, Doddatumakuru,

Estimated Cost: 30,00,000.00

Tender Amount : Rs. 24,22,022.59

Work Order No. EE/BTP/WO/02/2023-24 Dated: 12-12-2023.

Sl. No.	Item No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
1	E1	Supplying and fixing M15 grade precast cement concrete 600 x 300 x 150 mm Kerb Stone for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finsihed in line as per direction of Engineer in charge. (PWD SR 2021-22 Vol III Pg no 146 Item no 6.3)	Mtrs	250.00	443.34	110835.00	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - III	
2	E2	Painting Two Coats on New Concrete Surfaces Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concretesurfaces. MORTH Chapter 803 (PWD SR 2021-22 Vol III Pg no 56 Item No 8.10)	Sqm	100.00	100.62	10062.00	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - III	
3	E3	Removing and resetting of footpath slab (Approved arrival rate)	Sqm	252.45	223.91	56526.08	Additional Item	No	By over all savings in the work	Data Rate	
		Total				**177423.08**					

Percentage Excess $\frac{\textbf{177423.08}}{\text{Approved Tender Amoun } \textbf{2422109.73}} \times 100 =$ 7.33%

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Assistant Engineer
New Ward No. 10

Assistant Executive Engineer
Kodigehalli Sub Division

Executive Engineer
Byatarayanapura Division